



# Characterization of AZ31-NbC surface composite fabricated by friction stir processing

Muralimanokar M.<sup>1</sup>, Vaira Vignesh R.<sup>1</sup>, Padmanaban R.<sup>1</sup>, Suganya Priyadharshini G.<sup>2</sup>

- <sup>1</sup> Department of Mechanical Engineering, Amrita School of Engineering, Coimbatore, Amrita Vishwa Vidyapeetham, India
- <sup>2</sup> Department of Mechanical Engineering, Coimbatore Institute of Technology, Coimbatore, Anna University, India

E-mail: r.vairavignesh@gmail.com

AZ31D magnesium alloy is widely used in automotive, aircraft, and aerospace applications because of its high strength to weight ratio. However, the softness of the alloy results in higher wear rate and the high activity results in higher corrosion rate. With an aim of reducing the wear rate and corrosion rate of AZ31 alloy, surface composite of AZ31 alloy is fabricated by reinforcing niobium carbide (NbC) by friction stir processing. The microstructure and dispersion of the reinforcements in AZ31-NbC surface composite is analysed by optical microscopy. In addition, the microhardness and tribological characteristics of the developed AZ31-NbC surface composite are investigated. The results demonstrated an increase in microhardness (23.2 %) and the decrease in wear rate (15.6 % for a normal load of 2 kg) in the developed AZ31-NbC surface composite with respect to the base material. The immersion corrosion test was performed to analyse the corrosion rate of the developed AZ31-NbC surface composite in simulated sea water environment (3.5 wt % NaCl solution). The results indicate that the corrosion rate of the developed AZ31-NbC surface composite is higher than that of base material. A comprehensive analysis on the wear and corrosion mechanism of the developed AZ31-NbC surface composite is presented.

## INTRODUCTION

Magnesium alloys known for the light weightiness is broadly used in numerous engineering applications interfacial [1-3]. Magnesium is alloyed with aluminium, zinc, silicon, copper and rare earth metals to enable definite applications in automobile, aerospace, and optical components [2, 4]. Although magnesium alloys are used in structural applications, their poor corrosion and wear resistance limits their utility. This necessitated an expansion and manufacture of magnesium alloys with better strength and improved corrosion and wear property [5, 6]. One of the widely accepted technologies to obtain desired properties in the magnesium alloy is through fabrication of composites [7, 8].

Composites are materials that are fabricated by reinforcing one new phase in the base matrix. Composites are advantageous over conventional alloy systems, as the former possesses desired and better properties [9, 10]. Surface composites are suitable materials for engineering applications involving surface interactions. Surface composites results in augmented characteristics of composites on the surface while retaining properties of the base material.

Standard methods for formulating surface composites consist of liquid phase processing and at higher temperatures such as plasma spraying and laser melting. The high temperature favors reaction between metal matrix and the reinforcement. In addition, liquid-state processing lead to progressively degraded properties. Hence, solid-state processing of composites is beneficial. Friction stir processing is emerging as a promising technique for making surface composites [11, 12]. Mishra et al., reviewed the fabrication of surface composites by FSP [13-15]. The common reinforcements that are used to fabricate composites by FSP include CNT [16], MWCNT [17, 18], SiC [19, 20], SiO<sub>2</sub> [21, 22], ZrO<sub>2</sub> [21], HAP [23], Al<sub>2</sub>O<sub>3</sub> [24, 25], fly ash [26], TiC [27, 28] and WC [13, 29].

In this work, surface composite of AZ31 alloy is fabricated by reinforcing NbC using FSP. The study presents the evolution of microstructure, microhardness, corrosion rate and wear rate of the developed surface composite.

# **MATERIALS AND METHODS**

# Material

The base material used in the study was wrought magnesium alloy AZ31. The composition of the alloy is given in Table 1. The wrought plate was cut in to work-pieces of dimensions of  $150 \times 50 \times 4$  mm. A square groove of dimension  $1 \times 1 \times 100$  mm was machined on the workpiece to fill the reinforcements. Niobium Carbide (NbC) particles of ~30  $\mu$ m was used as reinforcement.

Tab. 1. Composition of AZ31 alloy

Mg	Al	Fe	Mn	Ni	Si	Zn	Cu
Bal.	3.3	0.007	0.25	0.0005	0.6	1.1	0.01

# Friction stir processing

The workpieces were cleaned with acetone before FSP trial. The reinforcements were filled in the groove and a sealing pass was performed using the sealing tool. Then FSP trials were performed on the specimens. A dwell time of 60 minutes was provided between the consecutive FSP passes. The optimum process parameters were obtained from previous research work (tool rotation speed of 1200 rpm and tool traverse speed of 45 mm/min using a sealing tool of shoulder diameter 18 mm and FSP tool of shoulder diameter of 18 mm; pin diameter of 5 mm and pin height of 3.5 mm).

## Microstructure analysis

Specimen of dimension  $10 \times 10$  mm were cut and were mounted using cold setting compound. Acetic picral was used as an etchant. The specimens were polished to obtain mirror finish. The etched surface was observed in an optical microscope at various magnifications.

#### Vickers microhardness

For micro hardness testing, the specimens were prepared as described in the microstructure analysis. The polished specimens were indented at a normal load of 100 gf for 15 seconds. The average of five microhardness measurements that were taken at different points in the stir zone of the developed surface composite is reported.

## Wear test

The specimens of dimension  $50 \times 20$  mm were cut and were mounted in a steel tube to make the pin. The

specimens were slid against EN31 steel disc at normal condition (temperature of 25 °C; dry condition). The test parameters were as follows: sliding velocity of  $0.6 \text{ m s}^{-1}$ , sliding distance of 597.6 m). The load was varied between 1 kg, 1.5 kg and 2 kg. The wear rate was calculated using the equation (1).

Wear rate = 
$$\frac{\Delta M}{F \cdot D}$$
 (1)

where  $\Delta M$  is Mass loss, F is normal load and D is sliding distance. The codes and details of the specimens is given in Table 2.

#### Immersion corrosion test

The corrosion test was performed for the developed surface composite specimen along with the base material. The specimens were into required dimension of  $10 \times 10$  mm and mirror-polished on all sides. The simulated sea water solution (3.5% NaCl solution) was prepared by mixing 35 g of NaCl in 1000 ml of distilled water. Eighteen specimens (nine from base material and nine from the developed surface composite) were placed in individual conical flask that was filled with 250 ml of simulated sea water. The conical flasks were placed in a thermostatic bath and maintained at 40 °C. The samples were cleaned in ultrasonicator filled with acetone. Three specimens were taken out from the conical flask (both from base material and developed surface composite) at an interval period of 24 hrs, 48 hrs, and 96 hrs. The mass loss was found out using a precision weight balance of readability 0.0001 g. The corrosion rate of the specimen was calculated using the equation (2).

Corrosion rate = 
$$\frac{K \cdot \Delta M}{A \cdot T \cdot D}$$
 (2)

where  $K = 8.76 \times 10^4$ ,  $\Delta M$  is mass loss, A is surface area, T is time, D is density of magnesium alloy. The codes of the specimens are given in Table 3.

Tab. 2. Wear test details

D-4-il-	Code	Wear test parameters			
Details	Code	Load (kg)	Sliding velocity (m/s)	Sliding distance (m)	
	B01	1.0	0.6	597.6	
Average wear rate of base material	B02	1.5	0.6	597.6	
	В03	2.0	0.6	597.6	
	F01	1.0	0.6	597.6	
Average wear rate of developed surface composite	F02	1.5	0.6	597.6	
arace composite	F03	2.0	0.6	597.6	

DOI: 10.2478/kom-2020-0005

Tab. 3. Immersion corrosion details

Details	Code	Immersion time (hours)
Average corrosion rate of base material	B24	24
	B48	48
	B96	96
Average corrosion rate	F24	24
f developed surface	F48	48
composite	F96	96

## **RESULTS AND DISCUSSION**

#### Microstructure

Figure 1a shows the un-etched microstructure of developed surface composite that shows the NbC reinforcement embedded in the matrix. The Figure 1b (etched) shows the dispersed  $\beta$ -Mg<sub>17</sub>Al<sub>12</sub> ( $\beta$ -phase), and fine grains in the developed surface composite. The dark patches show the fine distribution of NbC. No characteristic agglomeration of NbC was observed in the developed surface composite.

## **Microhardness**

The microhardness of base material was observed to be 56 Hy. The microhardness value of the developed surface composite specimen was found out to be 69 Hv, which indicated 23.2 % increase in hardness in the developed surface composite. The dispersion of  $\beta$  phase and NbC with grain refinement increased the hardness of the developed surface composite. The hardness of the nugget zone was found to be higher than that of the base material and thermo-mechanically affected zone.

## Wear rate

Figure 2 shows the wear rate of the base material and developed surface composite at various load conditions. The wear rate of the specimen B01 was  $5.339 \times 10^{-7}$  g/Nm at a normal load of 1 kg. The specimen B02 which was tested at the load of 1.5 kg had the wear rate of 1.2736 ×10-7 g/Nm, B03 had established wear rate of  $1.3987 \times 10^{-7}$  g/Nm at 2 kg of load.

The wear rate for the developed surface composite are lower than that of the base material at all the loads. F01 had the wear rate  $1.1281 \times 10^{-7}$  g/Nm with the normal load of 1 kg, F02 has the wear rate  $1.2192 \times 10^{-7}$  g/Nm




Fig. 2. Wear rate of the base material and developed surface composite at various loads





Fig. 1. AZ31-NbC surface composite: a) un-etched; b) etched



with the normal load of 1.5 kg and F03 has the wear rate  $1.1794 \times 10^{-7}$  g/Nm with normal load of 2 kg. The percentage decrease in wear rate of F01 is 78.8 %, F02 is 4.2 % and F03 is 15.6 % than that of the corresponding base material B01, B02, and B03. The details on the mode of wear is discussed in the following section

# **Surface morphology**

Figure 3 indicates the worn surface morphology of the specimen B03 that was worn at a load of 2 kg. Formation of wear debris in a clustered manner and minor cracks were observed, as shown in in Figure 3a. Deep grooves and cracks on the worn surface, as shown in Figure 3b, were created by the concentration of load in a localized spot. Figure 3c displays the furrows, mild cracks and scratches. Removal of material as a cut pieces lead to delamination, as shown in Figure 3d. Besides, ploughing phenomenon, which is caused by the dragging of debris in the course of the wear, was prevalent on the worn surface of the specimen. The results indicated

a combined adhesive and abrasive wear phenomenon in the specimen B03. Figure 4 shows the worn surface morphology of the specimen F03 that was worn at a load of 2 kg. Figure 4a shows the spalling on the worn surface that was chanced by the ejection of material in the form of small particles. Figure 4b picturizes the wear debris and Figure 4c shows the localized forms of wear (furrows and scratches). Shallow grooves and wear debris were observed in the Figure 4d. The specimen F03 exhibited comparatively lesser abrasive features than that of the specimen B03 that was slid at same load. Figure 5 shows the surface morphology of the worn specimen F01 that was worn at a load of 1 kg. Figure 5a shows pits and mild scratches. Some traces of wear debris are observed in Figure 5b. Material removal in the form of small piece of coatings and chips can be seen in the Figure 5c. Figure 5d clearly shows the wear debris, scratches. The wear mechanism of the developed surface compoiste was in the region of mild wear at low load and in the region of transition zone (adhesive wear and abrasive wear) at high loads.




Fig. 3. Surface morphology of B03 specimen




Fig. 4. Surface morphology of F03 specimen





Fig. 5. Surface morphology of F01 specimen (continue on next page)






Fig. 5. Surface morphology of F01 specimen

# Elemental composition analysis

Figure 6 shows the elemental composition of the specimen B03 that had the highest wear rate. The elements on the surface were Al, Mg, Zn, O. The count of Mg is high with the atomic concentration of 67.88 % and the oxygen content of 56.55 %. More count of O indicates the oxidation of the worn surface. Figure 7 displays the elemental composition of the worn region in F03 that was worn at a normal load of 2 kg. Occurrence of Al, Mg, O, with trace amount of Na is confirmed through the analysis. The atomic concentration of O (27.89 %) is higher next to Mg (69.90 %), indicating the predominant oxidation of the surface in the course of wear process. Figure 8 shows the elemental analysis of the worn out region in the specimen F01 with significant counts for Al, Mg, Zn, and O. The availability of Mg is high in this case with the atomic concentration of 65.55 % and the oxygen remains the next to Mg with an average atomic concentration of 33.45 %. This again indicates

the oxidation of the specimen during the course of wear. The elemental composition analysis reveals that the base material and developed surface composite undergo oxidation during the wear process.




Fig. 7. Elemental composition of F03 specimen




Fig. 6. Elemental composition of B03 specimen




Fig. 8. Elemental composition of F01 specimen

#### **Immersion corrosion test**

The corrosion rate of the base material and the developed AZ31-NbC surface composite specimen with the immersion time is shown in Figure 9. The corrosion rate of the surface composite-NbC is higher when compared to the base material. The specimen B24 had a corrosion rate of 0.0124 mm/year, B48 had a corrosion rate




Fig. 9. Corrosion rate of the base material and developed surface composite

of 0.01414 mm/year, and B96 had a corrosion rate of 0.1316 mm/year. The developed surface composite had a corrosion rate of 0.0218 mm/year, 0.4231 mm/year and 0.5006 mm/year after 24 hours, 48 hours and 96 hours of immersion. The corrosion rate of the developed surface composite is 3.8 times higher than that of the base material after 96 hours of immersion in simulated sea water solution. The corrosion rate drastically increased for the developed surface composite. This is attributable to the presence of Mg/NbC interfaces in the developed surface composite. The interfaces break the continuity of the magnesium matrix and hence create preferential sites for corrosion. Besides, the small radius of chloride ions favors preferential adsorption of chloride ions and formation of magnesium chloride. The higher solubility of magnesium chloride increases the new sites for corrosion and stimulates more dissolution of magnesium. Hence, the corrosion rate was fairly higher in the developed surface composite.

# **Surface morphology**

Figure 10a and 10b displays the surface morphology of developed surface composite AZ31-NbC alloy after 24 hours of corrosion test. Figure 10c and 10d shows the surface morphology of developed surface composite




Fig. 10. Corroded surface morphology of the base material and developed surface composite (continue on next page)






Fig. 10. Corroded surface morphology of the base material and developed surface composite

AZ31-NbC alloy tested for 48 hours of corrosion test. Figure 10e and 10f indicates the surface morphology of base material after 96 hours of corrosion test. In the surface morphology of the corroded specimen, the white patches correspond to the corrosion products. The overall analysis reveals the absence of pitting phenomena in the corroded specimen.





# **Elemental composition analysis**

The elemental composition analysis reveals that the major elements in the corroded specimen are Mg, O, Al, Zn. Based on the EDS analysis the corrosion mechanism of the base material and the developed surface composite are as follows.

$$Mg \rightarrow Mg^{2+} + 2e^{-} \tag{3}$$

$$2H_2O + 2e^- \rightarrow H2\uparrow + 2OH^-$$
 (5)

$$Mg^{2+} + 2OH^{-} \rightarrow Mg(OH)_{2}$$
 (6)

$$Mg^{2+} + 2Cl^{-} \rightarrow MgCl_{2}$$
 (7)

The interaction of specimen with the simulated sea water induces the formation of magnesium hydroxide as given by the equations (3) and (4). The tiny radius of Cl ions favours the adsorption of chloride ions on the surface of Mg(OH)<sub>2</sub>. It consequently favours the formation of MgCl<sub>2</sub> as given by equation (7). The corrosion rate drastically increased for the developed surface composite AZ31-NbC after 24 hours of corrosion. This attributes to the presence of Mg matrix/NbC that breaks the continuity of the Mg matrix and creating preferential




Fig. 11. Elemental composition analysis of developed surface composite AZ31-NbC: a) after 24 hours of corrosion; b) after 48 hours of corrosion; c) base material after 96 hours of corrosion

regions for corrosion, which is similar to the observation of Chan Chiu et al. [20]. This increases the corrosion rate of the developed surface composite than that of the base material.

# **CONCLUSION**

Friction stir processing was applied on AZ31 alloy with NbC reinforced to develop surface composite. The microhardness, corrosion, and tribological characteristics of the developed surface composites were investigated. The results demonstrated as follows:

- The microstructure shows the dispersed β-Mg17Al12 (β-phase), and fine grains in the developed surface composite, and the fine distribution of NbC were obtained.
- The microhardness of the base material is 56 Hv and that of the develop surface composite is 69 Hv.
- The wear rate of the developed surface composite is lower than that of the base material at all the test loads.
- The immersion corrosion results indicated that the corrosion rate of the surface composite is higher than that of the base material.

#### **REFERENCES**

- A. S. Handbook, Magnesium and magnesium alloys, ASM International 1999, pp. 106-118.
- M. K. Kulekci: Magnesium and its alloys applications in automotive industry, *The International Journal of Advanced Manufacturing Technology* 2008, 39, 851-865.
- 3. V. V. Ramalingam, P. Ramasamy, M. D. Kovukkal, G. Myilsamy: Research and development in magnesium alloys for industrial and biomedical applications: a review, *Metals and Materials International* **2019**, 1-22.
- W. J. Joost, P. E. Krajewski: Towards magnesium alloys for high-volume automotive applications, *Scripta Materialia* 2017, 128, 107-112.
- S. Mathaudhu, A. Luo, N. Neelameggham, E. Nyberg, W. Sillekens: Essential readings in magnesium technology, Springer: New York, 2016.
- D. S. Kumar, C. T. Sasanka, K. Ravindra, K. Suman: Magnesium and its alloys in automotive applications A review", *Am. J. Mater. Sci. Technol.* 2015, 4, 12-30.
- S. T. Peters: Handbook of Composites, Springer Science and Business Media, 2013.
- 8. S. Suresh: Fundamentals of metal-matrix composites, Elsevier: Amsterdam, 2013.
- P. S. Bains, S. S. Sidhu, H. Payal: Fabrication and machining of metal matrix composites: a review, *Materials and Manufacturing Processes* 2016, 31, 553-573.
- 10. M. Nováková, O. Chocholatý, A. Kříž: The influence of deformation on the corrosion properties of the material, *Koroze a ochrana materialu* 2017, 61, 86-90.
- R. S. Mishra, Z. Ma, I. Charit: Friction stir processing: a novel technique for fabrication of surface composite, *Materials Science and Engineering: A* 2003, 341, 307-310.
- 12. Z. Ma: Friction stir processing technology: a review, *Metallurgical and Materials Transactions A* **2008**, 39, 642-658.

- R. S. Mishra, Z. Ma: Friction stir welding and processing, *Materials Science and Engineering: R: reports* 2005, 50, 1-78.
- R. S. Mishra, M. W. Mahoney, Y. Sato, Y. Hovanski, R. Verma: Friction stir welding and processing VI: John Wiley and Sons: Hoboken, 2011.
- R. S. Mishra, P. S. De, N. Kumar: Friction stir welding and processing: science and engineering: Springer: New York, 2014
- J.-Y. Kim, J.-W. Hwang, H.-Y. Kim, S.-M. Lee, W.-S. Jung, J.-W. Byeon: Fabrication of AZ31/CNT surface nano-composite by double-pass friction stir processing, Archives of Metallurgy and Materials 2017, 62, 1039-1042.
- Y. Morisada, H. Fujii, T. Nagaoka, M. Fukusumi: MWCNTs/ /AZ31 surface composites fabricated by friction stir processing, *Materials Science and Engineering: A* 2006, 419, 344-348.
- M. Jamshidijam, A. Akbari-Fakhrabadi, S. M. Masoudpanah, G. H. Hasani, R. V. Mangalaraja: Wear behavior of multiwalled carbon nanotube/AZ31 composite obtained by friction stir processing, *Tribology Transactions* 2013, 56, 827-832.
- A. A. Nia, S. Nourbakhsh: Microstructure and mechanical properties of AZ31/SiC and AZ31/CNT composites produced by friction stir processing, *Transactions of the Indian Institute of Metals* 2016, 69, 1435-1442.
- C. Chiu, H.-C. Liu: Mechanical properties and corrosion behavior of WZ73 Mg Alloy/SiCp composite fabricated by stir casting method, *Metals* 2018, 8, 424.
- 21. C. Chang, Y. Wang, H. Pei, C. Lee, X. Du, J. Huang: Microstructure and mechanical properties of nano-ZrO<sub>2</sub> and nano-SiO<sub>2</sub> particulate reinforced AZ31-Mg based composites fabricated by friction stir processing, *Key Engineering Materials* 2007, 114-119.
- 22. V. V. R, P. R, and G. M: Synthesis and Characterization of Magnesium Alloy Surface Composite (AZ91D SiO<sub>2</sub>) by Friction Stir Processing for Bioimplants, *Silicon* **2019**, 6, 18.
- R. V. Vignesh, R. Padmanaban, M. Govindaraju, G. S. Priyadharshini: Mechanical properties and corrosion behaviour of AZ91D-HAP surface composites fabricated by friction stir processing, *Materials Research Express* 2019, 6, 085401.
- G. Faraji, P. Asadi: Characterization of AZ91/alumina nanocomposite produced by FSP, *Materials Science and Engi*neering: A 2011, 528, 2431-2440.
- D. Lu, Y. Jiang, R. Zhou: Wear performance of nano-Al<sub>2</sub>O<sub>3</sub> particles and CNTs reinforced magnesium matrix composites by friction stir processing, *Wear* 2013, 305, 286-290.
- 26. V. Kondaiah, P. Pavanteja, P. A. Khan, S. A. Kumar, R. Dumpala, B. R. Sunil: Microstructure, hardness and wear behavior of AZ31 Mg alloy fly ash composites produced by friction stir processing, *Materials Today: Proceedings* 2017, 4, 6671-6677.
- 27. M. Balakrishnan, I. Dinaharan, R. Palanivel, R. Sivaprakasam: Synthesize of AZ31/TiC magnesium matrix composites using friction stir processing, *Journal of Magnesium* and Alloys 2015, 3, 76-78.
- 28. M. Tang, Z. Feng, X. Wu, W. Wang, G. Li, Z. Yan, et al.: Microarc oxidation coatings containing TiC and NbC on magnesium alloy, *Surface Engineering* 2019, 1-9.
- V. Sharma, U. Prakash, B. M. Kumar: Surface composites by friction stir processing: A review, *Journal of Materials Processing Technology* 2015, 224, 117-134.